

**COUNTY OF IMPERIAL
SIDEWALK IMPROVEMENTS NEAR SAN PASQUAL
ELEMENTARY SCHOOL IN THE COMMUNITY OF
WINTERHAVEN IN IMPERIAL COUNTY; STATE PROJECT No.
SR2SL-5958 (083); COUNTY PROJECT No. 5511**

Notice to Prospective Interested Parties:

Addendum #2 (January 23, 2017) Issued by fax and telephone confirmation to CTJs, Department of Public Works website and by certified mail only to bidders who have purchased bid documents.

The following changes shall become part of the contract documents for this project and all other conditions shall remain the same:

**Item No. 1 Add the following:
Revised Engineer's Estimate**

Item No.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT COST	TOTAL COST
1	Traffic Control & Construction Area Signs	LS	1		
2	Asphalt Concrete	TON	220		
3	Demolition, Road Excavation, Hauling, and Earthwork	CY	480		
4	Class II Base	TON	670		
5	PCC Curb & Gutter	LF	1,050		
6	PCC Concrete Driveway - 12'	EA	1		
7	PCC Concrete Driveway - 20'	EA	3		
8	PCC Sidewalk	SF	5,400		
9	Driveway & Sidewalk Transition - Class II Base	TON	180		
10	Striping & Signage	LS	1		
11	Surveying	LS	1		
12	Storm Drain Catch Basin	EA	1		
13	Erosion Control	LS	1		

Total _____

Item No. 2 Clarification

Bid Item No 12 was revised to say Storm Drain Catch Basin

Concrete shall be 4000 PSI minimum compressive strength. Joint details shall be per details shown on the improvement plans.

The storm drain Catch Basin shall be constructed on 4" minimum Class II aggregate base compacted to 95% minimum relative compaction over 6" of native soil scarified and recompacted to 85% minimum relative compaction, presoaked to minimum 20% moisture prior to concrete placement and as shown elsewhere in the improvements plans. Furnishing and placement of Class 2 AB material shall be considered as included in the

unit price for storm drain manhole. If necessary, the contractor is required to bring additional fill material to ensure specified storm drain manhole grade is met. Any such work will be at expense of contractor.

Full compensation for furnishing all labor, materials, barricades, tools and equipment and all work included in the construction of storm drain manhole sawcutting, and disposing of same, 4" Class II aggregate base, scarifying 6" native soil and recompacting and replacement of any required fill material and minor restorative grading shall be included in the contract price paid per storm drain catch basin and no additional payment will be made therefore.

**Item No. 3 The following shall be part of Section 10-1.08
Demolition, Roadway Excavation, Hauling & Earthwork**


Required sidewalk embankment to provide smooth transition (3 ft instead of 5 ft shown on plans detail) to match existing elevation. This will consist of the of the placing and compacting Class II base within the back of sidewalk. Full compensation for furnishing all labor, materials, barricades, tools and equipment and all work included in the placement of Class II base for this work shall be included in the contract price paid per ton of Driveway & Sidewalk Transition and no additional compaction shall be therefore.

Item No. 4 Clarification on the Curb inlet length

The curb inlet length is 9 feet

The general contractor is responsible for advising any and all subcontractors of this change. Each bidder must acknowledge receipt of this addendum in the noted space below and where indicated on the Bidders Bond Section of the Special Provisions. Addendum No. 2 must be attached to the proposal.

Acknowledgement of Addendum #2



John A. Gay, PE
Director of Public Works

Print or Type Company Name

Print or Type Authorized Name

Authorized Signature of Contractor

Date Signed