



Public Works works for the Public



COUNTY OF  
IMPERIAL

**COUNTY OF IMPERIAL PUBLIC WORKS**

155 S. 11<sup>th</sup> Street  
El Centro, CA 92243

DEPARTMENT OF  
PUBLIC WORKS

**County of Imperial Department of Public Works  
Imperial County Health Department Re-Roofing System  
Located At 935 Broadway Ave., El Centro, CA**

155 S. 11th Street  
El Centro, CA  
92243

**County Project No. SR6214HTH**

Tel: (442) 265-1818  
Fax: (442) 265-1858

**ADDENDUM NO. 5**

**NOVEMBER 15, 2016**

This *ADDENDUM* is hereby made part of the Contract Documents and specifications to the same extent as if originally included therein, and shall be signed by the Bidder and included with the proposal.

**NOTIFICATION: The Bid Opening date has been extended to December 2, 2016 at 3:00 P.M.**

**Sealed bids shall be received at the office of the Clerk of the Board of Supervisors at the County Administration Center, located at 940 Main Street, Suite 209, in El Centro, CA 92243, no later than 3:00 P.M. on December 2, 2016.**

**Clarification No. 1:** Remove and dispose of the existing wood sleepers and replace them with new, appropriately-sized Pipe Guard Supports supplied by OMG or approved equal.

**Clarification No. 2:** The HVAC unit located at the far west end of the building that is ballasted on deteriorating wood sleepers shall be raised to allow for the installation of the PVC roof membrane. The unit shall be then reset upon new treated wood sleepers, matching the same size as the existing sleeper. The new sleepers shall be encapsulated with flashing membrane and welded to the field sheet. The top of the encapsulated wood sleeper shall have walk tread adhered to it, cut and sized to fit properly. The HVAC unit shall then be reset upon the new waterproofed and protected sleepers.

**Clarification No. 3:** Remove and clean out all caulk from the newer, existing coping metal and replace it with new Sikasil WS-295 or approved equal.

**Clarification No. 4:** Abandoned pitch pockets shall be removed and disposed. No asbestos has been found. Infill the newly-created opening with suitable compatible materials per industry standards.

**Clarification No. 5:** At the perimeter edge, install new 'Reflective Gray' clad metal by Sarnafil or approved equal over the existing galvanized edge metal. The face of the new clad metal shall extend down no greater than 2" in length.

**Clarification No. 6:** All material/products identified in the bid documents by a manufacturer or trademark may be substituted with a pre-approved equal subject to the Architect's review and approval.

**Question No. 1:** Substitution Request pursuant to Section 07 50 00 Part 2, Section 2.02 Membrane. Thermal and Moisture Protection, Mech Fast FB PVC Membrane for the use of the Johns Manville 80 mil Fleece Back PVC Membrane - JM PVC 80 FB roofing system - ASTM 4434 Type III product.

*Response No. 1: The Johns Manville product has been rejected as a substitution by the Architect.*

**Question No. 2:** Substitution Request pursuant to Section 07 50 00 Part 2, Section 2.02 Membrane for the use of Carlisle SynTec – Sure-Flex PCV product.

*Response No. 2: The Carlisle product has been rejected as a substitution by the Architect.*

The Contractor is responsible for advising any and all subcontractors of this change. Each bidder must acknowledge receipt of this addendum in the noted space below and must be attached to the proposal.



John A. Gay, PE  
Interim Director of Public Works

**Acknowledgement of Addendum No. 5**

License No: \_\_\_\_\_

Print or Type Company Name: \_\_\_\_\_

Print or Type Authorized Name: \_\_\_\_\_

Authorized Signature of Contractor: \_\_\_\_\_

Date Signed: \_\_\_\_\_